new englan	© ISO New England, Inc. 2024	Master/LCC Procedure No. 15 - System Operating Limits Methodology, Attachment C Revision Number: Rev 4.4 Revision Date: September 11, 2024
Owner: ISO Director, Operations Support		Approved by: M/LCC Heads
Services		Review Due Date: September 11, 2025

Attachment C - Contingency Impact Evaluation

Table of Contents

l.	Contingency Impact Evaluation	. 2
M/L	_CC 15 Attachment C Revision History	. 3

This document is controlled when viewed on the ISO New England Internet web site. When downloaded and printed, this document becomes **UNCONTROLLED**, and users should check the Internet web site to ensure that they have the latest version.

Hard Copy Is Uncontrolled Page 1 of 3

Revision 4.4

ISO new england	© ISO New England, Inc. 2024	Master/LCC Procedure No. 15 - System Operating Limits Methodology, Attachment C Revision Number: Rev 4.4 Revision Date: September 11, 2024
Owner: ISO Director, Operations Support		Approved by: M/LCC Heads
Services		Review Due Date: September 11, 2025

I. Contingency Impact Evaluation

The following presents the general philosophy/method for determining if a contingency will have unacceptable Inter RCA/BAA impact.

- 1. Simulate the contingency.
- 2. Identify any elements that are overloaded at or above their STE rating.
- Open each STE overloaded element and rerun the EMS powerflow or other loadflow application.
 - A. Do not perform any manual switching of reactive devices between cascade steps
- 4. Repeat steps 2) and 3) and determine Inter RCA/BAA impact as follows:
 - A. If the element STE overloads/openings stop and the case solves without severe voltage/reactive conditions (such as voltage at or below 328 kV on the 345 kV system or voltage at or below 207 or 104 kV, respectively, on the 230 / 115 kV systems), Inter RCA/BAA impact is acceptable.
 - Treat as an IROL if either of the following post-contingent conditions occur:
 - When voltage on two or more non-radial 345 kV stations is below 95% of nominal voltage (328 kV) or
 - When transmission stations serving 500 MW or more net load have post-contingent voltage at or below 95% of nominal voltage on the 345 kV system, or less than 90% of nominal voltage on the 230 or 115kV systems.
 - In outage coordination, note the scope of voltages at or below the above noted thresholds
 - B. If the element STE overloads/openings continue to the point where an element in the New York ISO RCA/BAA becomes overloaded at or above its LTE rating, [STE allowed for underground cable circuits (except NNC, Y49, Y50 901 and 903 circuits, which are cable circuits)] unacceptable Inter RCA/BAA impact is indicated.
 - C. If the element STE overloads/openings continue to the point where the case will **not** solve, demarcate the subarea in the New England Transmission System that would separate from the rest of the system. This should be based on the cascading overload pattern evidenced by the load flows. Then go back to the original case and calculate the net power flow into or out of the subarea that would be separated. Unacceptable Inter RCA/BAA impact is possible if the subarea is supplying ≥ 1,200 MW to the rest of the system or if it is absorbing ≥ 1,200 MW of power. If the subarea is supplying < 1,200 MW or absorbing < 1,200 MW, the contingency would **not** have unacceptable Inter RCA/BAA impact.

ISO new england	© ISO New England, Inc. 2024	Master/LCC Procedure No. 15 - System Operating Limits Methodology, Attachment C Revision Number: Rev 4.4 Revision Date: September 11, 2024
Owner: ISO Director, Operations Support		Approved by: M/LCC Heads
Services		Review Due Date: September 11, 2025

M/LCC 15 Attachment C Revision History

<u>Document History</u> (This Document was created from the retired OP-19 Appendix G)

	Reason	
09/02/12	Initial draft	
08/30/13	Annual review performed by Procedure Owner, no changes to content required;	
04/04/14	Annual review by Procedure owner, no changes required at this time; Completed the administrative changes required to publish a Minor Revision;	
03/04/15	Annual review by Procedure owner, no changes required at this time; Completed the administrative changes required to publish a Minor Revision;	
02/29/16	Annual review by Procedure owner, no changes required at this time; Completed the administrative changes required to publish a Minor Revision;	
01/19/17	Annual review by Procedure owner, no changes required at this time; Completed the administrative changes (including adding required corporate identity to all footers) required to publish a Minor Revision;	
12/11/17	Annual review by Procedure owner, no changes required at this time; Completed the administrative changes required to publish a Minor Revision;	
11/28/18	Annual review by Procedure owner, no changes required at this time; Completed the administrative changes required to publish a Minor Revision;	
11/05/19	Annual review by Procedure owner; Globally made editorial changes based on changes in the conditions, practices and management expectations;	
10/26/20	Annual review by Procedure owner; Account for consistent treatment of low voltage in IROL assessments	
12/21/20	Clarified IROL determination criteria in Section I.4.A	
09/27/21	Annual review by Procedure owner proxy, no changes required at this time; Completed the administrative changes required to publish a Minor Revision;	
09/19/22	Annual review by Procedure owner, no changes required at this time; Completed the administrative changes required to publish a Minor Revision.	
09/13/23	Annual review performed by procedure owner requiring no intent changes; Minor formatting changes; Made administrative changes required to publish a Minor Revision.	
09/11/24	Annual review performed by procedure owner requiring no changes; Made administrative changes required to publish a Minor Revision.	
	08/30/13 04/04/14 03/04/15 02/29/16 01/19/17 12/11/17 11/28/18 11/05/19 10/26/20 12/21/20 09/27/21 09/19/22 09/13/23	

Revision 4.4 Page 3 of 3
ISO-NE PUBLIC